



**FIRE PUMP EQUIPMENT SCHEDULE**

UNIT No.	MODEL	TYPE	QTY	LOCATION	CAP m <sup>3</sup> /hr EACH	HEAD IN METERS EACH	POWER CONSUM. EACH	POWER SUPPLY V PHz	REMARKS
FP-01	AURORA - USA 6-481-16H1	HORIZONTAL SPLIT CASE	1	BASEMENT-2 FLOOR	227m <sup>3</sup> /hr	125	200	415 3 50	WORKING
FP-02	AURORA - USA 6-481-16H1	HORIZONTAL SPLIT CASE	1	BASEMENT-2 FLOOR	227m <sup>3</sup> /hr	125	200	415 3 50	STANDBY
JP-01	EMARA - ITALY EMO50/50FS	VERTICAL	1	BASEMENT-2 FLOOR	115m <sup>3</sup> /hr	130	7.5kw	415 3 50	WORKING

**TRANSFER AND IRRIGATION PUMP EQUIPMENT SCHEDULE**

S.No	Description	Identification	Location	Capacity	Remark
1.	Domestic Transfer pump-Basement-2	TP	Basement-2	Capacity: 5m <sup>3</sup> /hr @ 110MR TDH (2 Duty + 1 Standby)	
1.	Domestic Transfer pump-Basement-2	TP	Basement-2	Capacity: 5m <sup>3</sup> /hr @ 110MR TDH (2 Duty + 1 Standby)	
3.	Irrigation supply Booster pump	IRP	Basement-2	Capacity: 3m <sup>3</sup> /hr @ 55MR TDH (1 Duty + 1 Standby)	

